Navi Mumbai airport build-out

Navi Mumbai International Airport site, Maharashtra | Before - Sentinel-2 - 2019-01-13 to After - Sentinel-2 - 2024-12-17

What we found

We found 265 real changes covering 251 hectares. The biggest and strongest (rank 1) is new construction: 21.59 ha at 18.9996, 73.0817.

By priority: 17 Critical, 35 High, 69 Medium, 144 Low.

The detector first flagged 2,185 candidate areas. The rest were removed as false alarms: seasonal crop and vegetation cycles, tiny specks and noise, change types this analysis does not track, cloud and cloud shadow.



Numbers = rank of the 10 highest-priority changes. Outline colour = priority.

Changes by priority

Critical	17
High	35
Medium	69
Low	144

Totals

Area changed: 251 ha

Cropland affected: 157 ha (upper bound)

Built-up land affected: 2.51 ha

How to read this report

Rank	Every change has a number. Rank 1 is the highest priority: the largest and strongest change. Priority = size x strength of the change.
Priority colour and shape	Critical (octagon): score 20,000 or more (about 2 ha of strong change); High (diamond): score 5,000 or more; Medium (square): score 1,500 or more; Low (circle): score below 1,500 (small or weak).
Confidence	How sure the system is that the change is real, from 0 to 100 %. Changes marked 'needs a human check' sit between 50 % and 70 %.
What changed	New construction, vegetation cleared, vegetation growth, new water / flooding, water receded, or unexplained change. These come from rules on the satellite colours, not from knowing what is actually on the ground.
Raw detections	Everything the detector first flagged. Most are not real (clouds, crop seasons, shadows, specks), so only changes that pass the filters are listed here.

The 10 highest-priority changes

Start here. Each card says where the change is, how big it is, why it was flagged and what to do.

1

New construction

Rank 1 of 265 | Critical priority

Size	21.59 ha (215,850 m2), about 30 football pitches
Confidence	90 %
Location	18.99956, 73.08168 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	SWIR/blue ratio (paved surfaces are flatter) fell (-0.32)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



2

New construction

Rank 2 of 265 | Critical priority

Size	16.95 ha (169,550 m2), about 24 football pitches
Confidence	94 %
Location	19.00075, 73.05531 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	built-up index fell (-0.05), water index rose (+0.07), SWIR/blue ratio (paved surfaces are flatter) fell (-0.75)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



3

New construction


Rank 3 of 265 | Critical priority

Size	15.86 ha (158,550 m2), about 22 football pitches
Confidence	89 %
Location	18.99408, 73.06718 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	SWIR/blue ratio (paved surfaces are flatter) fell (-0.36)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After




4

New construction


Rank 4 of 265 | Critical priority

Size	13.53 ha (135,300 m2), about 19 football pitches
Confidence	93 %
Location	18.99295, 73.05575 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	SWIR/blue ratio (paved surfaces are flatter) fell (-0.44)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



5

Water receded


Rank 5 of 265 | Critical priority

Size	9.61 ha (96,100 m2), about 13 football pitches
Confidence	97 %
Location	18.99084, 73.06284 (open in Google Maps)
What it is	Water that was there before has gone.
Why flagged	built-up index rose (+0.17), vegetation index rose (+0.22), water index fell (-0.38), SWIR/blue ratio (paved surfaces are flatter) rose (+1.63)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



6

New construction

Rank 6 of 265 | Critical priority

Size	10.79 ha (107,900 m2), about 15 football pitches
Confidence	93 %
Location	18.99877, 73.04909 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	water index rose (+0.05), SWIR/blue ratio (paved surfaces are flatter) fell (-0.66)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



7

New construction

Rank 7 of 265 | Critical priority

Size	8.00 ha (79,950 m2), about 11 football pitches
Confidence	94 %
Location	18.99012, 73.08238 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	vegetation index fell (-0.11), water index rose (+0.13), SWIR/blue ratio (paved surfaces are flatter) fell (-0.71)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



8

New construction

Rank 8 of 265 | Critical priority

Size	8.25 ha (82,500 m2), about 12 football pitches
Confidence	92 %
Location	18.98663, 73.06099 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	water index rose (+0.06), SWIR/blue ratio (paved surfaces are flatter) fell (-0.66)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



9

New construction

Rank 9 of 265 | Critical priority

Size	7.24 ha (72,350 m2), about 10 football pitches
Confidence	91 %
Location	18.99456, 73.04540 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	SWIR/blue ratio (paved surfaces are flatter) fell (-0.53)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



10

New construction

Rank 10 of 265 | Critical priority

Size	6.59 ha (65,950 m2), about 9 football pitches
Confidence	91 %
Location	19.00214, 73.06037 (open in Google Maps)
What it is	Land that was open (vegetation or bare soil) now looks built-up: roofs, roads or concrete.
Why flagged	water index rose (+0.07), SWIR/blue ratio (paved surfaces are flatter) fell (-0.63)
What to do	Check first. A large, strong change; send someone or review recent imagery now.

Before



After



All 265 changes found

Every change that survived the false-alarm filters, in priority order (rank 1 is the highest). A * after the confidence means it needs a human check. The CSV and GeoPackage downloads hold the same list with every attribute.

Rank	Priority	What changed	Size (ha)	Confidence	Latitude	Longitude
1	Critical	New construction	21.59	90 %	18.99956	73.08168
2	Critical	New construction	16.95	94 %	19.00075	73.05531
3	Critical	New construction	15.86	89 %	18.99408	73.06718
4	Critical	New construction	13.53	93 %	18.99295	73.05575
5	Critical	Water receded	9.61	97 %	18.99084	73.06284
6	Critical	New construction	10.79	93 %	18.99877	73.04909
7	Critical	New construction	8.00	94 %	18.99012	73.08238
8	Critical	New construction	8.25	92 %	18.98663	73.06099
9	Critical	New construction	7.24	91 %	18.99456	73.04540
10	Critical	New construction	6.59	91 %	19.00214	73.06037
11	Critical	New construction	5.59	95 %	18.99001	73.07510
12	Critical	Water receded	4.88	96 %	18.98429	73.06487
13	Critical	New construction	6.62	85 %	18.99825	73.07224
14	Critical	New construction	5.13	91 %	18.99043	73.06720
15	Critical	New construction	3.67	94 %	18.98774	73.05740
16	Critical	New construction	3.84	92 %	18.99853	73.08567
17	Critical	Water receded	4.18	88 %	19.00244	73.04301
18	High	Water receded	1.83	99 %	18.98202	73.04644
19	High	New construction	3.06	89 %	18.99063	73.06079
20	High	New construction	2.65	93 %	18.99568	73.07407
21	High	New construction	2.52	94 %	18.97892	73.04219
22	High	New construction	2.54	91 %	18.98792	73.07231
23	High	New construction	2.14	94 %	19.00290	73.08062
24	High	New construction	2.27	89 %	18.97790	73.05848
25	High	New construction	1.74	93 %	18.99658	73.05154
26	High	New construction	1.90	88 %	18.98439	73.05322
27	High	New construction	1.52	94 %	18.97562	73.04164
28	High	New construction	1.38	95 %	18.98745	73.04739
29	High	New construction	1.65	89 %	18.99703	73.07924
30	High	Water receded	1.81	85 %	18.99853	73.05333
31	High	New construction	1.70	86 %	18.98428	73.04851
32	High	Water receded	1.30	93 %	18.97589	73.09715
33	High	Water receded	1.31	92 %	18.99447	73.08920
34	High	New construction	1.20	93 %	19.00291	73.09763
35	High	Water receded	1.14	94 %	18.97571	73.05153
36	High	New construction	1.44	84 %	19.00173	73.07354
37	High	New construction	1.41	84 %	18.99772	73.06686
38	High	New construction	0.96	96 %	18.98610	73.04836
39	High	New construction	0.96	94 %	18.98673	73.04954
40	High	New construction	0.90	95 %	18.99894	73.04172
41	High	New construction	0.97	92 %	18.99261	73.08585
42	High	New construction	0.76	97 %	18.96556	73.09388
43	High	New construction	0.65	98 %	18.99243	73.08294
44	High	Water receded	0.66	98 %	18.98229	73.06610
45	High	New construction	0.64	98 %	18.97508	73.08695
46	High	New construction	0.79	95 %	18.99838	73.04363
47	High	New construction	1.01	87 %	18.98929	73.06179
48	High	New construction	0.85	92 %	18.98443	73.05131

Rank	Priority	What changed	Size (ha)	Confidence	Latitude	Longitude
49	High	Water receded	0.70	96 %	19.00408	73.09604
50	High	New construction	0.82	91 %	18.98677	73.07045
51	High	New construction	0.97	84 %	18.99933	73.06151
52	High	New construction	0.86	89 %	18.99163	73.08619
53	Medium	New construction	0.71	94 %	18.97958	73.04986
54	Medium	New construction	0.81	90 %	18.99669	73.04764
55	Medium	New construction	0.76	92 %	19.00128	73.07100
56	Medium	New construction	0.88	86 %	18.98424	73.05466
57	Medium	New construction	0.80	90 %	18.99997	73.09778
58	Medium	New construction	0.90	82 %	18.99282	73.07270
59	Medium	Water receded	0.46	98 %	18.98313	73.06145
60	Medium	New construction	0.68	90 %	18.99916	73.05979
61	Medium	New construction	0.58	95 %	19.00801	73.09724
62	Medium	New construction	0.72	86 %	18.99276	73.06429
63	Medium	New construction	0.69	88 %	18.99114	73.08511
64	Medium	New construction	0.75	84 %	18.99116	73.06428
65	Medium	New construction	0.51	96 %	18.99229	73.04470
66	Medium	New construction	0.65	90 %	18.97561	73.08559
67	Medium	New construction	0.76	81 %	18.98781	73.07852
68	Medium	New construction	0.52	95 %	18.96700	73.04098
69	Medium	Water receded	0.57	90 %	19.00390	73.08749
70	Medium	New construction	0.55	92 %	18.98859	73.09198
71	Medium	New construction	0.36	99 %	18.98827	73.05592
72	Medium	New construction	0.51	93 %	18.98568	73.09665
73	Medium	New construction	0.51	92 %	18.97933	73.07754
74	Medium	New construction	0.54	89 %	18.97995	73.09121
75	Medium	New construction	0.47	93 %	18.97975	73.05159
76	Medium	New construction	0.49	91 %	18.98539	73.08216
77	Medium	Water receded	0.39	96 %	19.00701	73.05767
78	Medium	New construction	0.46	91 %	19.00978	73.09500
79	Medium	New construction	0.41	94 %	18.96886	73.07907
80	Medium	New construction	0.39	96 %	18.97276	73.08033
81	Medium	Water receded	0.41	93 %	19.00210	73.05041
82	Medium	New construction	0.28	99 %	18.98894	73.05426
83	Medium	Water receded	0.41	93 %	18.98382	73.04356
84	Medium	New construction	0.38	95 %	18.98310	73.07778
85	Medium	Water receded	0.36	96 %	18.99544	73.08723
86	Medium	New construction	0.39	94 %	18.96895	73.05363
87	Medium	New construction	0.28	98 %	18.98787	73.05401
88	Medium	New construction	0.53	80 %	18.97716	73.08528
89	Medium	New construction	0.41	88 %	18.97970	73.08557
90	Medium	New construction	0.38	90 %	18.97669	73.05495
91	Medium	New construction	0.39	89 %	19.00065	73.04737
92	Medium	New construction	0.38	89 %	18.98548	73.07854
93	Medium	Water receded	0.27	97 %	19.00564	73.05937
94	Medium	New construction	0.35	90 %	18.99269	73.09022
95	Medium	New construction	0.32	92 %	19.00508	73.09458
96	Medium	New construction	0.32	92 %	18.98896	73.08452
97	Medium	New construction	0.34	90 %	18.98993	73.07935
98	Medium	New construction	0.25	97 %	18.98046	73.05069
99	Medium	New construction	0.34	88 %	18.97818	73.05580

Rank	Priority	What changed	Size (ha)	Confidence	Latitude	Longitude
100	Medium	New construction	0.23	98 %	18.97376	73.09965
101	Medium	New construction	0.30	90 %	19.00306	73.09397
102	Medium	New construction	0.30	90 %	18.97968	73.06048
103	Medium	New construction	0.33	87 %	18.98490	73.05498
104	Medium	New construction	0.21	98 %	18.99966	73.04873
105	Medium	New construction	0.18	99 %	18.99133	73.07642
106	Medium	New construction	0.35	83 %	18.99221	73.04824
107	Medium	New construction	0.34	84 %	18.98587	73.05486
108	Medium	New construction	0.28	91 %	18.97975	73.05400
109	Medium	Water receded	0.34	83 %	18.99413	73.08596
110	Medium	Water receded	0.20	98 %	18.98181	73.05537
111	Medium	Water receded	0.25	94 %	18.96920	73.05928
112	Medium	New construction	0.32	85 %	18.98363	73.04213
113	Medium	New construction	0.29	88 %	18.99076	73.07912
114	Medium	New construction	0.23	95 %	18.97218	73.07736
115	Medium	New construction	0.18	98 %	18.98573	73.04671
116	Medium	New construction	0.24	92 %	18.98700	73.05283
117	Medium	New construction	0.28	88 %	18.98735	73.08246
118	Medium	New construction	0.24	92 %	18.98092	73.05277
119	Medium	Water receded	0.28	86 %	18.98232	73.06938
120	Medium	New construction	0.17	98 %	18.98455	73.04308
121	Medium	New construction	0.18	98 %	18.98822	73.06845
122	Low	New construction	0.32	79 %	18.99502	73.04109
123	Low	New construction	0.21	95 %	18.99199	73.05902
124	Low	New construction	0.27	86 %	19.00259	73.07726
125	Low	Water receded	0.32	79 %	18.97968	73.06281
126	Low	New construction	0.16	98 %	18.97426	73.10013
127	Low	New construction	0.27	85 %	18.99490	73.07593
128	Low	New construction	0.28	83 %	18.98823	73.07738
129	Low	New construction	0.21	94 %	18.97945	73.04784
130	Low	New construction	0.24	89 %	18.99537	73.08859
131	Low	New construction	0.20	94 %	18.98634	73.08666
132	Low	New construction	0.21	93 %	19.00011	73.08603
133	Low	New construction	0.23	91 %	18.96758	73.05899
134	Low	New construction	0.23	91 %	18.98301	73.09497
135	Low	New construction	0.23	90 %	18.99375	73.08486
136	Low	New construction	0.26	85 %	18.99532	73.04283
137	Low	Water receded	0.14	99 %	18.97687	73.06916
138	Low	New construction	0.18	96 %	18.98375	73.04866
139	Low	New construction	0.24	86 %	18.99004	73.06976
140	Low	New construction	0.15	98 %	19.01482	73.08630
141	Low	New construction	0.27	80 %	18.99756	73.06928
142	Low	New construction	0.21	90 %	18.97417	73.05034
143	Low	New construction	0.17	95 %	19.00895	73.09598
144	Low	New construction	0.15	98 %	18.98157	73.05025
145	Low	New construction	0.24	84 %	18.98719	73.06680
146	Low	New construction	0.22	88 %	18.99728	73.08996
147	Low	New construction	0.15	97 %	18.98766	73.05293
148	Low	New construction	0.24	84 %	18.97006	73.04184
149	Low	New construction	0.21	89 %	18.98896	73.08850
150	Low	Water receded	0.25	81 %	18.97906	73.05970

Rank	Priority	What changed	Size (ha)	Confidence	Latitude	Longitude
151	Low	Water receded	0.18	93 %	18.99572	73.05958
152	Low	New construction	0.12	99 %	18.98908	73.05501
153	Low	New construction	0.12	99 %	18.98231	73.05594
154	Low	New construction	0.21	87 %	18.97041	73.05642
155	Low	New construction	0.21	86 %	19.00109	73.07614
156	Low	New construction	0.21	85 %	18.99460	73.06216
157	Low	New construction	0.12	99 %	18.98743	73.04900
158	Low	New construction	0.23	82 %	18.98310	73.04983
159	Low	New construction	0.21	85 %	18.97333	73.08545
160	Low	New construction	0.15	95 %	18.96845	73.04784
161	Low	New construction	0.18	90 %	18.99266	73.04385
162	Low	New construction	0.12	98 %	18.98069	73.05192
163	Low	New construction	0.15	94 %	19.00047	73.04300
164	Low	New construction	0.14	96 %	18.98361	73.04789
165	Low	New construction	0.18	88 %	19.00068	73.05848
166	Low	New construction	0.17	88 %	18.98673	73.09299
167	Low	New construction	0.16	91 %	18.99252	73.04130
168	Low	Water receded	0.15	92 %	18.98461	73.04661
169	Low	New construction	0.15	92 %	18.97784	73.08182
170	Low	New construction	0.14	94 %	18.99129	73.04299
171	Low	New construction	0.15	90 %	18.98804	73.08243
172	Low	New construction	0.14	94 %	19.00014	73.04232
173	Low	New construction	0.19	82 %	18.96914	73.05603
174	Low	New construction	0.15	91 %	18.98609	73.04972
175	Low	New construction	0.12	96 %	18.99773	73.08776
176	Low	New construction	0.12	96 %	18.97883	73.04672
177	Low	New construction	0.15	90 %	18.98274	73.09302
178	Low	New construction	0.12	96 %	18.97866	73.06937
179	Low	New construction	0.18	81 %	18.98886	73.07806
180	Low	New construction	0.15	89 %	18.99240	73.05715
181	Low	New construction	0.17	83 %	19.00012	73.06133
182	Low	New construction	0.09	99 %	18.99172	73.04424
183	Low	New construction	0.09	99 %	18.96797	73.08013
184	Low	New construction	0.09	98 %	18.96843	73.08050
185	Low	New construction	0.15	87 %	18.97935	73.09244
186	Low	New construction	0.12	94 %	19.00592	73.09788
187	Low	New construction	0.14	88 %	18.97586	73.05453
188	Low	New construction	0.15	85 %	19.00109	73.04252
189	Low	New construction	0.14	88 %	19.00061	73.04163
190	Low	New construction	0.15	85 %	18.98301	73.04890
191	Low	New construction	0.17	76 %	18.99006	73.06422
192	Low	New construction	0.09	98 %	18.96637	73.07359
193	Low	New construction	0.09	98 %	18.98918	73.08691
194	Low	New construction	0.09	98 %	18.99633	73.05293
195	Low	New construction	0.14	86 %	18.97125	73.04141
196	Low	New construction	0.12	91 %	18.97113	73.05740
197	Low	New construction	0.14	84 %	18.98482	73.06033
198	Low	New construction	0.09	97 %	18.97354	73.07655
199	Low	New construction	0.09	97 %	18.99832	73.04464
200	Low	New construction	0.09	97 %	18.97752	73.09426
201	Low	New construction	0.15	79 %	18.99431	73.07593

Rank	Priority	What changed	Size (ha)	Confidence	Latitude	Longitude
202	Low	New construction	0.12	89 %	18.99250	73.05843
203	Low	New construction	0.12	89 %	18.98113	73.06426
204	Low	Water receded	0.12	88 %	19.00283	73.07826
205	Low	New construction	0.12	88 %	19.00588	73.09859
206	Low	New construction	0.09	96 %	18.96910	73.07537
207	Low	New construction	0.09	96 %	18.98513	73.04668
208	Low	New construction	0.09	96 %	18.98910	73.05254
209	Low	New construction	0.12	87 %	18.97847	73.06040
210	Low	New construction	0.09	96 %	18.98153	73.06326
211	Low	New construction	0.09	96 %	18.97188	73.07306
212	Low	New construction	0.09	95 %	18.97791	73.06292
213	Low	New construction	0.12	85 %	19.00234	73.07484
214	Low	New construction	0.09	95 %	18.98834	73.04979
215	Low	New construction	0.12	85 %	18.99715	73.07514
216	Low	New construction	0.12	85 %	18.99280	73.09138
217	Low	New construction	0.09	94 %	18.97536	73.07767
218	Low	New construction	0.09	94 %	18.97077	73.07962
219	Low	New construction	0.12	84 %	18.99779	73.08520
220	Low	New construction	0.12	84 %	18.97734	73.08145
221	Low	Water receded	0.09	94 %	18.98037	73.06460
222	Low	New construction	0.09	94 %	18.97500	73.07786
223	Low	New construction	0.09	94 %	19.00363	73.09539
224	Low	New construction	0.09	93 %	18.98811	73.09652
225	Low	New construction	0.12	82 %	18.99594	73.08935
226	Low	New construction	0.12	82 %	18.99346	73.05923
227	Low	New construction	0.12	82 %	18.98892	73.07889
228	Low	New construction	0.12	82 %	18.99865	73.05447
229	Low	New construction	0.09	92 %	18.97778	73.09350
230	Low	Water receded	0.09	92 %	18.99647	73.05796
231	Low	New construction	0.12	81 %	18.98448	73.07809
232	Low	New construction	0.09	92 %	18.97695	73.04024
233	Low	New construction	0.09	92 %	18.98628	73.05152
234	Low	New construction	0.09	92 %	18.98829	73.09613
235	Low	New construction	0.09	91 %	18.96583	73.04739
236	Low	New construction	0.12	79 %	18.99701	73.07087
237	Low	New construction	0.09	91 %	18.97626	73.08602
238	Low	New construction	0.09	91 %	18.96506	73.04370
239	Low	New construction	0.12	78 %	18.97183	73.08217
240	Low	New construction	0.09	90 %	18.98961	73.09270
241	Low	New construction	0.09	90 %	19.00379	73.08437
242	Low	New construction	0.09	89 %	18.99733	73.08862
243	Low	New construction	0.12	74 %	18.99652	73.08051
244	Low	New construction	0.09	88 %	18.98634	73.03994
245	Low	New construction	0.09	87 %	19.00067	73.07111
246	Low	New construction	0.09	87 %	18.97529	73.05393
247	Low	New construction	0.09	86 %	18.96709	73.04690
248	Low	New construction	0.09	86 %	19.00182	73.07670
249	Low	New construction	0.09	85 %	18.98913	73.04684
250	Low	Water receded	0.09	85 %	18.96615	73.04416
251	Low	New construction	0.09	84 %	18.99321	73.09171
252	Low	Water receded	0.09	84 %	18.97102	73.05208

Rank	Priority	What changed	Size (ha)	Confidence	Latitude	Longitude
253	Low	Water receded	0.09	84 %	19.00297	73.04915
254	Low	New construction	0.09	82 %	19.00100	73.05914
255	Low	New construction	0.09	82 %	18.99520	73.08333
256	Low	New construction	0.09	82 %	18.99421	73.04099
257	Low	New construction	0.09	82 %	18.98669	73.05598
258	Low	New construction	0.09	80 %	18.99688	73.06223
259	Low	New construction	0.09	80 %	18.99517	73.07174
260	Low	New construction	0.09	80 %	18.98921	73.09840
261	Low	New construction	0.09	80 %	18.98492	73.05923
262	Low	New construction	0.09	79 %	18.98618	73.05836
263	Low	New construction	0.09	77 %	19.00857	73.05744
264	Low	New construction	0.09	76 %	18.99621	73.06774
265	Low	New construction	0.06	90 %	18.96464	73.04171

Data sources

- Copernicus Sentinel-2 L2A (ESA), via the Element84 Earth Search COG bucket
- ESA WorldCover 2021 v200 (10 m), CC-BY 4.0

Limits - what this report cannot tell you

- Optical imagery cannot see through cloud; flagged areas with cloud are removed, not analysed.
- Change type comes from spectral index rules (no training); check critical changes on the ground.
- 10 m pixels cannot resolve single small buildings or people.
- Land cover is ESA WorldCover 2021, newer than the before image (2019): land already cleared or under construction can be mislabelled as cropland, so treat cropland as an upper bound
- Buildings and road segments need OpenStreetMap, which was not reachable when this result was built: shown as unknown, not zero
- This report points to where to look. Confirm important changes on the ground before acting.